

Mask Integrity

Where Lithography Begins

Understand. Align. Innovate. Develop.

Effective Solutions for In-Fab EUVL Mask Cleaning

Tobias Wähler, Sherjang Singh, Uwe Dietze
(HamaTech APE)
Rik Jonckheere, Bart Baudemprez
(IMEC)

2010 International Symposium on
Extreme Ultraviolet Lithography

Topics

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

Agenda

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

Background

EUV Mask Life Cycle



Source: ASML, HamaTech-APE

Background

EUVL Specific Challenges





	EUV Reflectivity	CD shift (non-uniformity)	Litho Fidelity/Stability	Mask Life Time
Ru Oxidation	↓	↓	↓	↓
C deposition	↓	↓	↓	↓
Particles		↓	↓	

Goal → **Restore** → **Remove** → **Preserve**

Agenda

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

Infrastructure Aspects

EUVL Mask Maintenance at IMEC



Phase 1:

- Receive masks in standard 193i shipping boxes
- Manual load into ADT storage box (SB) before cleaning
- Automated load into ADT SB after cleaning

Phase 1 completed!



- *Eliminates manual handling of cleaned masks*
- *Limitation of shipping and manual handling remains*

Infrastructure Aspects

EUVL Mask Maintenance at IMEC



Phase 2:

- Totally avoid manual handling !!!
- Establish compatibility with EUV pod-in-pod
- Retain flexibility for variable input/output and transfer between:
  - Pod-in-Pod
  - ADT SB
  - SMIF





Infrastructure Aspects

Understand. Align. Innovate. Develop.

EUVL Mask Maintenance at IMEC

Phase 1 (completed) Phase 2



Agenda

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

EUVL Mask Cleaning

EUVL Mask Cleaning POR Established at IMEC



SPM Free Cleaning!

Agenda

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

Experimental Cleaning Results

Carbon Removal Performance



Before Clean



After 1x POR Clean



- A synchrotron was used to intentionally deposit carbon contamination
- Carbon contamination was *removed by 1x POR clean*

Data provided by SAMSUNG

Experimental Cleaning Results

PRE Performance on SiN Particles

Before Clean



After 1x Clean



- POR applied to EUV blank
- Process yielded *>99 % PRE on first pass*
- Confirmed with further cleans





Data provided by SAMSUNG

Experimental Cleaning Results

PRE Performance on Natural Particle Contamination (IMEC Defect 32-2)





Soft & Hard Defects

Hard Defects remain

- POR applied to EUV pattern mask
- Cleaning process yielded *>97 % PRE on first pass*
- *< 1 adder* per clean average (based on wafer defect analysis of repeat cleans)
- Remaining defects are non-removable in repeat cleaning and match typical level of absorber/blank/mask related hard defects
- *No hard defects added* (based on wafer defect analysis of repeat cleans)

Experimental Cleaning Results

Conventional DIO3 Cleaning vs. POR (Blank Vendor A)



See also Poster: R. Lebert et al. „Contributions to EUV mask metrology infrastructure: Reflectometer, Blank Inspection and DPP+LPP EUV Sources“

- 10x Conventional DIO3 process caused substantial deterioration of EUV reflectivity. Magnitude suggests complete Ru removal and ML damage.
- 10x POR cleaning resulted in a *slight EUV reflectivity improvement*.

Experimental Cleaning Results



Note reflectivity scale!

- *EUV reflectivity still slightly increased* even after 20x POR
- Slight reduction in EUV reflectivity between 10x and 20x POR may be due to:
  - Repeatability of metrology
  - Slight ML reflectivity change
  - Unequal rate of organic surface material accumulation

Experimental Cleaning Results

XPS Analysis (Blank Vendor A)

	C	RuO	Ru	Si	Mo	SiO	S	O
Virgin	17.69	9.25	22.81	11.12	0.71	3.91	1.4	33.1
10x POR	26.29	9.69	18.03	10.83	0.87	3.29	0	31

Values in %

	C	RuO	Ru	RuO+Ru
Virgin	0.33	0.66	1.63	2.29
10x POR	0.49	0.89	1.44	2.33

Values in nm

- XPS material analysis suggests only *minor changes in surface layer structure*
- XPS based material thickness modeling *confirms integrity of Ru capping layer*
- Acid-free POR shows *good Sulfur removal* capability

Note: Elevated Carbon signature on 10x cleaned sample may be due to difference in sample handling prior to XPS

Experimental Cleaning Results

EUV Reflectivity and AFM Surface Roughness (Vendor A)

- **Raw surface roughness (2μ x 2μ AFM scans)**





- *Slight improvement* in surface quality observed after *5x clean*
- *No degradation* of surface roughness observed throughout *10x clean*
- *Slightly higher* EUV reflectivity after *10x clean*

Experimental Cleaning Results

CD Uniformity Signature (Pattern EUV Mask on Blank Vendor B)





- *No significant change* in CD signature observed throughout *10x clean*
- CD uniformity improves slightly after first two cleans
- CD uniformity constant between clean 2 and clean 10

Experimental Cleaning Results

CD Mean (Pattern EUV Mask on Blank Vendor B)



- *No* change in CD mean up to *2x clean*
- *Slight* change in CD mean after *4x clean*
- *Dramatic* CD mean shift after *10x clean*

Note: 10% CD shift exceeds the predicted effects of complete Ru loss (ML damage?)

Experimental Cleaning Results

Potential Root Cause for CD Mean Shift After 10x Clean

- Partial damage or weakening of Ru through exposure to aggressive resist strip and cleaning during mask manufacturing
- Ru structure altered due to residual moisture on mask during EUV exposure
- Cleaning process conditions changed unnoticed
- Electrolytic erosion of Ru through surrounding TaBN absorber
- Difference in Ru structure of blanks provided by Vendor A vs. Vendor B

Further Investigation is needed!

Agenda

- Background
- Infrastructure Aspects
- EUVL Mask Cleaning
- Experimental Cleaning Results
  - Carbon Removal
  - Particle Removal
  - Surface Integrity
- Summary & Conclusions

Summary

- EUV masks are contaminated during use (average of > 5 adders per week found when utilizing existing 193i infrastructure)
- Conventional DIO3 based cleaning quickly damages Ru capping
- Mask cleaning POR established at IMEC demonstrates improved results:
  - Complete removal of EUV induced Carbon with 1x clean
  - No detectable degradation in EUV reflectivity after 20x clean
  - High stability in ML structure (based on XPS)
  - No increase in surface roughness of Ru (based on AFM)
  - PRE > 97% for natural defects (handling, storage) and > 99% for SiN
  - Low particle adder rate (cleaning and ADT pod transfer)
  - No detectable feature damage after 10x clean
  - No significant CD uniformity shift after 10x clean
- Unusual CD mean shift on pattern mask requires further investigation!

Conclusions

- The useful lifetime of an EUV mask depends on:
  - Durability of surface layers (especially capping)
  - Choice of cleaning methods
  - Frequency of cleaning (MTBC - Mean Time Between Cleans)
  - Acceptable ML performance loss
- Optical properties of ML can be maintained if proper cleaning techniques are employed (*> 50x clean cycles within reach based on current results!).*
- Blank material may have significant impact on surface layer durability (further studies are needed)
- Other factors, such as mask manufacturing techniques and EUV exposure conditions (e.g. residual moisture on mask surface) need further investigation
- Pod-in-pod infrastructure urgently needed for:
  - Mask shop backend of line
  - Shipping between mask shop and fab
  - In-fab Storage
  - In-fab transfer (e.g. between Storage/Clean/Inspection and Scanner)

Acknowledgement

- **Daehyuk Kang, Hanshin Lee and Jinhong Park of Samsung for data and metrology support**
- **Ted Liang, Robert Chen, Sang Lee and Todd Younkin of Intel for data and metrology support**
- **Rainer Lebert of Bruker for EUV reflectivity metrology and data analysis**
- **CATRENE EXEPT for its support of EUVL technology development throughout Europe**

Understand.

Align.

Innovate.

Develop.

Our customers' success is our responsibility